Offer Number MEGA/OFFER/26-27/594 17th September 2026

Purchaser : Unipro Techno Infrastructure Pvt. Ltd.
Project : Pipeline Infrastructure Project
Manufacturer : M/s. Mega Pipes Pvt Limited (Jabalpur)

Sr. No.	Types of pipes	Specifications	Description		Quantity	Unit Price of Pipe or	Total Price of pipes on D
			OD (MM)	WT (MM)	MTR	INR/Mtr	INR
1	HSAW Coated	IS3589 Fe 410	1243	8.4	2,000	22,351	4,47,02,000
2	HSAW Coated	IS3589 Fe 410	1317	8.4	350	23,570	82,49,500
3	HSAW Coated	IS3589 Fe 410	1367	8.4	500	24,396	1,21,98,000
4	HSAW Coated	IS3589 Fe 410	1417	8.4	4,400	25,220	11,09,68,000
TOTAL					**7,250**		**17,61,17,500**

Total Amount in Words: Rupees Seventeen Crore Sixty One Lakh Seventeen Thousand Five Hundred Only

All taxes and duties like GST shall be extra at actuals. The prevailing rate at the time of dispatch shall be levied. Current Rate of GST is 18%.

TERMS & CONDITIONS

	Our Price CIF for Krishna Nagar, Bagodar, Jharkhand - 825322
Price	The prices are offered are in meter basis.
Scope of Supply	Manufacture & Supply of Coated MS (HSAW) Pipes conforming to IS 3589. Pipes will be manufactured & supplied from our Jabalpur Plant in MP. External Coating- PU 1000 Micron, Internal coating- FGE 406 micron. Dispatch will be on stacking basis we have not considered Nesting.
Price Validity	Offer is valid for placement of order for 5 days (i.e. 15th September 2026), thereafter subject to our written reconfirmation.
Payment Terms	The Payment terms offered are 25% Advance and Balance against Letter of Credit. The LC to be established within 7 days of PO placement.
TDS Under 194Q	The buyer is responsible for deducting TDS under section 194Q. The TDS Amount needs to be deposited with the tax authorities & it is the responsibility of the buyer to ensure TDS certificates are submitted in a timely manner each quarter.
Raw Material Procurement	Procurement of raw materials will commence upon receipt of PO, Advance or QAP whichever is received later. Any delay in LC opening & increase in raw material prices during procurement will affect finalized rates.
Interest	Any delay in payments transfer shall attract interest at 12% pa. Delay beyond agreed date shall attract penal interest @ 15% pa.
Weight of Pipes	The weight of pipes at the weighment bridge of Mega-Pipes shall be considered final.
Quantity Variation	Any change/variation in ordered quantity/wall thickness to max +/- 5% shall be confirmed within 10 days of PO but before coil receipt.
Quantity Tolerance	Quantity tolerance to the tune of +/- 3 pipes item-wise. LC should allow quantity/value tolerance accordingly.
Delivery	Commencement of production shall be within 45 to 60 days from PO date, LC opening & QAP approval whichever is later. Production completed within 60 days from commencement.
Packing & Forwarding	Pipes supplied LOOSE without packing as per standards. Unloading at site in your scope. Transporter provides 24 hours for unloading; delay results in demurrage.
Part Order	Prices considered are for full quantity, Part order not acceptable.
Freight	Considered with maximum loading of pipes on trailer. Lesser pipes sent will result in proportionate freight increase.
Logistic Conditions	If unloading site is in a remote area with narrow access, trailers deliver to nearest accessible highway; subsequent transport in customer scope.
Guarantee	Material guaranteed against manufacturing defects for 12 months from date of Inspection Release Note.
Cancellation Schedule	If order cancelled before raw material procurement, advance adjusted towards damages. If after procurement, all HR coil damages in customer account.
Force Majeure	Supply subject to standard Force Majeure conditions beyond reasonable control.
Pipe Length	Min 90% of pipes between 11 & 12 meters; max 10% between 9 & 11 meters.
Thickness Tolerance	No negative tolerance on thickness as per IS 8329 / IS 3589.
Ovality of Pipes	D/T <= 100: 1% of OD; D/T > 100: 2% of OD.
Testing	Third Party Inspection charges in buyer's scope.
Inspections	Testing carried out in our in-house lab at plant. Mill Test Certificate provided. Free in-process TPI access provided.
Technical	Proposal based on IS 3589 Fe 410 / API 5L Equivalent specification.
Skelp joint	Skelp joint considered as allowed by BIS standard.
Steel Origin	Steel procured from approved mills: JSW, AMNS, Tata Steel, Jindal Steel & Power, SAIL, NMDC.
Steel Coil Rate	Based on today's HR coil market rate, subject to prevailing rate at order finalization.

For Mega Pipes Pvt. Limited

Authorized Signatory